



ADDENDUM #2

RFP NUMBER: 2014020-PU-P

North River Pump Station Upgrade Construction/Installation RFP

PROJECT 473-12-13

CONTRACT 1

DATE: February 28, 2014

TO: All Potential Proposers

City of Harrisonburg's North River Pump Station Upgrade Construction/Installation RFP (2014020-PU-P), is modified as follows:

1. Drawing M-101: Basis of design for louvers referenced in Notes 1 and 3 is Ruskin ELF375X, all welded aluminum construction, standard frame and bird screen. Baked enamel finish.
2. Duct systems shall be in accordance with SMACNA's "HVAC Duct Construction Standards –Metal and Flexible" latest edition. Comply with SMACNA for acceptable materials, material thickness, duct construction methods, support and installation unless otherwise indicated. Fabricate for 2 inch positive and negative pressure and seal class A.
3. Drawings M-101 and M-601: These drawings are schematic in nature and indicate the general and approximate location of equipment and ductwork. Contractor shall coordinate with the installation of work with the work of other trades and all necessary allowances and provisions shall be made by the Contractor for beams, columns, trusses or other obstructions of the building or the work of other contractors whether or not same is indicated. Where necessary to avoid obstruction ducts shall be transformed, offset, raised or lowered with the required free area being maintained. Provide control wiring per NEC and inside rigid steel conduit. All miscellaneous material required to ensure proper installation of ducts and equipment per manufacturers recommendations (unless otherwise noted) shall be furnished and installed by the Contractor.

End of Addendum No. 2

All other requirements, terms and conditions of the RFP remain unchanged.

Addendum page must be signed and returned with your proposal to acknowledge receipt of this addendum.

Authorized Signature

By: Pat Hilliard, CPPB
Purchasing Agent
