



ADDENDUM #2

ITB/RFP NUMBER: 20170027-PW-B

Harrisonburg Solid Waste Transfer Station ITB

DATE: October 21, 2016

TO: All Potential Bidders/Offerors

City of Harrisonburg's Solid Waste Transfer Station ITB, is modified as follows:

Please find posted separately a revised set of Site Plans dated 10-11-16 to replace the current plans.

1. Question: There is an existing pile of organic material, located in the vicinity of the proposed storm water pond, that is not shown on the topographic survey. Will this material be removed by others prior to site mobilization or will the sitework contractor be responsible to remove/use this material?

Answer: This is not a pile of organic material, it is a clay stockpile that is available for use by the site contractor.

2. Question: I assume access to all existing buildings must be maintained throughout the duration of the project?

Answer: The City will be as flexible as possible to allow for access to these buildings to be limited during certain phases of construction.

3. Question: What will be the mill and overlay requirements on Beery Road when tying in the proposed entrance?

Answer: Any mill and overlay will be limited to 2" milling and replacement with 2" of SM-9.5AL.

4. Question: The bidding documents call for the site to be bid as unclassified excavation. Is the site considered also unclassified for excavation below the subgrade?

Answer: Yes.

All other requirements, terms and conditions of the ITB/RFP remain unchanged.

Addendum page must be signed and returned with your bid/proposal to acknowledge receipt of this addendum.

Authorized Signature

By: Pat Hilliard, CPPB
Procurement Manager